

LANDSCAPING
Pre-Planting
 Make sure that the sub-soil is not over compacted after completion of the build. If this is the case the problem should be alleviated with the use of a deep plough or subsoil. This action should go down to a minimum depth of 600mm to allow drainage.

During Planting
Bare Root Plants
 The roots of all bare rooted plants should be kept covered at all times during the planting phase. If left unprotected - even for a few minutes the plant may be killed.

Standard Trees
 Where standard trees are being planted it is expected that these will not exceed 1.8m in height. These should be planted no deeper than the top level of the container. The tree must also be tied to a 300mm max wooden stake.

Planting Aids
 There are various materials that have shown in the past that can assist in the successful establishment for a great proportion of plants in a landscape scheme. These include; Plastic Tubes to place on small trees to protect and help to grow. Various types of planting mats to reduce competition for nutrients from grass, these can dramatically improve growth rates. Shrub beds should have mulched organic material mixed into the soil bed to a min of 150mm, materials such as peat, shredded bark and wood chippings are ideal.

POST PLANTING
 The following operations are essential for the successful establishment of any landscaping. Provision of these methods is essential for at least five seasons after the initial planting.

Weed Control
 Should be undertaken at least twice yearly for the season after planting. It is most important on shrub beds to keep unwanted grass and pest vegetation to a minimum. In addition trees or shrubs planted in a grass area should always be kept clear from an area of at least half a metre from the trunk. Using mulch mats greatly reduces the need to carry out weeding and also aids growth speed.

Watering
 The most common way in which lack of care causes the death of plants is neglect of watering in the first summer season. At least five waterings a month are needed in the warm dry spell from June-August, exceptions must be made if the summer is wet or too dry.

Replacement of Dead Plants
 If the above pre-planting, planting and post planting guides are adhered to, replacing plants in the first two seasons would likely be unnecessary. Normally, 5 to 10% of plants will need replacing during the first two years following planting, although by using container grown plants and increasing watering schedules this can be cut to virtually zero.

HEDGE PLANTING
 Mixed species hedge to be planted where indicated or where needed to augment existing boundary hedges.

Preparation
 Ground to be thoroughly de-compacted by hand prior to planting.

Stock
 see specification table

Density
 Double staggered row at 450mm centres.

Support & protection
 Protection against rabbits and deer damage - individual Tubex tree shelters of an appropriate size, staked and secured to incorporate rabbit wire at base.

Establishment
 Planting to take place next winter (November onwards).
 For two years after planting, maintain an area of 1sqm weed-free around each new plant, either by hand or application of suitable herbicide.
 Irrigation in the first year, depending on weather conditions.


Maintenance
 Pruning of tips on planting and future pruning, depending upon growth.
 Any trees that die or become diseased within 10 years of planting to be replaced to the above specification.

Levels
 Rear gardens to be leveled to average heights. Minor adjustments for construction tolerances to be finalised on site, e.g. up to 300mm either way

THIS LAYOUT HAS BEEN PREPARED WITHOUT THE BENEFIT OF A FULL UNDERGROUND AND OVERGROUND SERVICES SURVEY AND MAY BE SUBJECT TO CHANGE IF SERVICES ARE FOUND SUBSEQUENTLY.
 IF FULL ACCESS TO ALL BOUNDARIES WAS NOT POSSIBLE, FINAL DIMENSIONS TO BOUNDARIES & LEVELS WILL BE SUBJECT TO FURTHER CONFIRMATION

KEY

- 1800 C/Boarded Fence
- 1000 Post + Rail Fence or metal estate fencing
- Existing Trees
- Proposed Trees
- Proposed Native Hedging
- Proposed Shrubs + Borders
- Shingle Finish
- Tarmacadam Finish
- Paving
- Air Source Heat Pump
- Fixed External Light (low-glare downward beam)
- Electric Vehicle Infrastructure & Charging Point



EXACT PRIVATE ROAD SPECIFICATION to be confirmed by the Appointed Contractor in line with Suffolk Highways standard Specifications and Requirements, where applicable.

TYPICAL SPECIFICATION TABLE - minimum depth shown	PRIVATE DRIVEWAY	ACCESS ROAD
SURFACE	25mm	30mm
BINDER	50mm	70mm
SUB-BASE	150mm	225mm
DIG DEPTH	225mm	325mm

TREE PLANTING SCHEDULE

SPECIES	ROOT	HEIGHT
Weeping Flowering Crab Apple (Malus 'Sun Rival')	PDT	150-200cm
Silver Birch (Betula pendula)	PDT	150-200cm
Copper Beech (Fagus sylvatica f. purpurea)	PDT	150-200cm


TYPICAL SHRUBS & BORDER PLANTING SCHEDULE (mix as necessary)

SPECIES

- Lanlum Maculatum (White Nancy)
- Prunus Pink Perfection (Flowering Cherry)
- Photinia (Christmas Berry / Red Robin)
- Buddleja lindleyana (Butterfly Bush)
- Rhododendron 'Purple Splender'
- Hydrangea involucrata 'Hortensis' (hydrangea)
- Hostas
- Salvia 'Purple Majesty'
- 'Hardy' Lavender
- Rosemary
- Griselinia littoralis
- Mahonia japonica

HEDGE PLANTING SCHEDULE

SPECIES	DENSITY	AGE	ROOT	HEIGHT
30% Blackthorn (Prunus spinosa)	0.45m	1+ or 1/1	BR	40-60cm
30% Beech (Fagus sylvatica)	0.45m	1+ or 1/1	BR	40-60cm
10% Guelder Rose (Viburnum opulus)	0.45m	1+ or 1/1	BR	40-60cm
10% Dog Rose (Rosa canina)	0.45m	1+ or 1/1	BR	20-30cm
5% Wild Honeysuckle (Lonicera periclymenum)	0.45m	1+ or 1/1	BR	20-30cm
5% Holly (Ilex aquifolium)	0.45m	1+ or 1/1	CG-31	40-60cm
20% Hazel (Corylus avellana)	0.45m	1+ or 1/1	BR	40-60cm



A. 04.07.22 Reduction to 4 units
 Ref. Date Revision

Ensure all dimensions are checked on site prior to ordering of prefabricated elements. Ensure minimum headroom requirements are met for all staircases. Do not scale from this or any other drawing. Any discrepancies, contact the issuer. This drawing or any of its contents cannot be used except with the express written permission of the issuer. Without such permission no responsibility is taken for its content.

ROBERTS MOLLOY
 architects & consultants

3 church lane
 bressingham diss
 norfolk
 IP22 2AE

ROBERTS MOLLOY LIMITED ©
 Tel: 01379 687705
 E-mail: info@robertsmolloy.co.uk

PROJECT:
 WELLINGTON ROAD
 EYE

TITLE:
 PROPOSED
 BLOCK PLAN

Scale: 1:200@A1 Date: OCT 21

JOB No. EWR DRG No. 09A

Proposed scheme June 2023 bungalow.dwg